

GENERAL

The Facilities Planning and Construction Department will assign Room Numbers to all Spaces during the review of the Design Development Phase. These numbers will be on the Construction Bid Documents and can be used under doors and hardware, etc.

This broadscope Section can include building directories, door signs, address signs, and similar directional material and generally is used when more than one of those items will be required. A narrowscope Section dealing with the particular item is common when only one item (such as Building Director) is required. Be careful not to include the following items here, Subcontractors wouldn't expect to find them in this Section.

- a. Identification systems, especially for piping, should be in the Section 01080 of the General Requirements or in an appropriate Section in division 15.
- b. Project Signs should be specified along with other temporary facilities in Division 1.
- c. Pavement marking, including graphics, should be in Division 2.

Design Requirements

Provide plastic laminate door signs in accordance with the Duval County Public Schools standard format, patterns, color, and size. Provide standard machine cut letters and numbers. Signs should be mechanically fastened to wall by screws.

Sign shall include F.I.S.H. numbers. Coordinate with F.I.S.H. Coordinator at Phase II or Phase III Review.

Fire Alarm Sending Station located inside student occupied spaces, a permanently affixed sign reading "FIRE ALARM PULL STATION INSIDE" shall be placed outside that space, adjacent to the door. This sign shall have a red background with white letters.

Fire Extinguisher located inside student occupied spaces, a permanently affixed sign reading, "FIRE EXTINGUISHER INSIDE" shall be placed outside that space adjacent to the door. This sign shall have a red background with white letters.

These signs shall be located approximately 5 ft (152 cm) above the floor landing in a position that is readily visible when the door is in the open or closed position. All signs shall meet ADA Standards, including raised Braille. The Design Professional shall include directional signs for direction of public through Corridors to destination together with identification of specific function rooms such as, MEN, WOMEN, CUSTODIAL, CLOSET, MECHANICAL ROOM, DEPARTMENTAL NAMES, HIGH VOLTAGE, etc. Particular attention should be given placement of Exit signs to ensure compliance with Occupancy Limits at specific areas. Coordinate F.I.S.H. numbers prior to Phase III.

The Main School Sign - Located at the major access on the site, may be constructed of the same masonry material as used in the construction of the building. Lighting will be provided. The sign will have a message board. Lettering to be Helvetica Medium Font, size to be verify

Maximum Occupancy Signs – signs should be posted outside of the space adjacent to the main entrance/exit doors – (Provide as per SREF)

Room Signage

Provide a permanently affixed room number sign beside each door. These signs must comply with ADA requirements and DCSB Design Guidelines. Signs shall be frameless type from 1/8" laminated plastic, 4" square with square corners, white on black color. Characters shall be raised. Number shall be Helvetica Medium, 1-1/2" high. Letters shall be Helvetica medium style, 1/2" high. Room signs shall be mounted on the wall adjacent to the latch side of the room entrance door approximately 5' above finish floor and shall include engraved braille cell.

Provide additional signage at entrances for spaces such as administration, gymnasium, auditorium, cafeteria, media center, guidance, teacher dining, etc. where project scope dictates.

A room number and signage list, meeting State of Florida FISH requirements; will be provided to the Contractor by the Design Professional.

Parking signs shall be minimum 6 feet to bottom--provide adequate number of parking signs. Provide adequate wheel clearance from curb or wheelstop. "\$250 Fine" sign shall be incorporated under larger parking sign. Traffic signs shall meet State DOT Standards and ADA Requirements.

END OF SECTION 10440